BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

SCHDULE-B

Name of Work:-Improvements to drain at 5th &1st B cross road at Difence colony in Ward 14, Bagalagunte

Sl	Description of Work	Unit	Qty	Sanctioned Rates		Amount
				In figures (Rs)	In Words (Rs)	
1	2	3	4	5	6	7
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	**58.95**	90.72	Rupees Ninty & Seventy two Paise Only	5348.00
2	Removing B.S.Slab of drain and stacking etc., complete	**Sqm**	212.22	50.11	Rupees Fifty & Eleven Paise only	10635.00
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per	Cum	**61.90**	4211.38	Rupees Four thousand two hundred eleven and thirty eight Paise only	260674.00
4	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	**28.98**	4690.50	Rupees Four Thousand six hundred ninty & fifty Paise Only	135948.00
5	Refixing stone slabs of drains and pointing in CM 1:3 etc complete	**Sqm**	212.22	70.04	Rueeps seventy & four paise only	14863.00
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 thick	**Sqm**	141.48	343.44	Rupees Three hundred forty three & forty four Paise only	48590.00

Executive Engineer.

Signature of the contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

7	Providing and constructing precast **concrete solid blocks** with compressive strength not les than 35 Kg/sq[illegible] with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size **40x20x20** cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	**Sqm**	**314.40**	924.48	Rupees Nine hundred twenty four & Forty eight Paise Only	290657.00
8	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	**353.70**	1600.00	Rupees One thousand Six hundred Only	565920.00
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	**58.95**	78.24	Rupees Seventy eight & Twenty four Paise only	4612.00
					Total	**1337247.00**
					KRIDL Charges	162000.00
					misc	753.00
					Grand Total	**1500000.00**

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer